

„Balkan Route: A Welcoming Transit - AID 012590/02/7”
 „Balkanska ruta: Prijem u tranzitu (BRAT) – AID 012590/02/7”

LOT 3: Tehničko održavanje skladišta u Tuzli – bravarski radovi
 LOT 3: Technical maintenance of the warehouse in Tuzla – metalworking

A Predmjer radova za tehničko uređenje skladišta u Tuzli - bravarski radovi
Bill of quantities for the technical maintenance of the warehouse in Tuzla - metalworkings

A1 Radovi na objektu skladišta - PVC stolarija na skladištu
Works on warehouse building - PVC joinery in the warehouse

I BRAVARSKI RADOVİ
METALWORKS

Red. broj	Opis Description	JM Unit	Količina Number of units	Jedinična cijena bez PDV-a (KM) Unit cost VAT excluded (KM)	Ukupno bez PDV-a (KM) Total VAT excluded (KM)
1	2	3	4	5	6
1	<p> nabavka materijala, izrada i montaža PVC jednokrilnih prozora dimenzija 110 x 180, profil 80mm 6 komora, sa pripadajućim okovima, otvaranje oko horizontalne i vertikalne ose, staklo LOWe 4-16-4 LOWe punjeno argonom, U=1,3 W/m²K, termički prekinuti most.</p> <p>Cijenom obuhvatiti unutrašnju i vanjsku PVC klupicu.</p> <p>Obračun po komadu.</p> <p>Procurement of materials, fabrication, and installation of PVC single-leaf windows with dimensions 110 x 180 cm, 80mm profile, 6 chambers, with corresponding hardware, opening around the horizontal and vertical axis, glass LOWe 4-16-4 LOWe filled with argon, U=1.3 W/m²K, thermally broken bridge.</p> <p>The price should include both interior and exterior PVC sills.</p> <p>Calculation per piece</p> <p>Dimenzija:110x180cm</p> <p>Dimensions:110x180cm</p>	kom pcs	3		

2	<p>Nabavka materijala, izrada i montaža PVC jednokrilnih prozora dimenzija 80 x 180, profil 80mm 6 komora, sa pripadajućim okovima, otvaranje oko horizontalne i vertikalne ose, staklo LOWe 4-16-4 LOWe punjeno argonom, U=1,3 W/m²K, termički prekinuti most.</p> <p>Cijenom obuhvatiti unutrašnju i vanjsku PVC klupicu.</p> <p>Obračun po komadu.</p>	kom pcs	11		
3	<p>Nabavka materijala, izrada i montaža PVC dvokrilnih vrata dimenzija 190x210cm, profil 80mm 6 komora, okov poluoliva sa cilindar bravom i min 3 ključa, staklo ispuna 24 mm, ispuna kombinacija staklo/panel.</p> <p>Obračun po komadu.</p>	kom pcs	1		
UKUPNO ZA I) BRAVARSKI RADOVI TOTAL FOR I) METALWORKS					
REKAPITULACIJA RECAPITULATION					
I	BRAVARSKI RADOVI METALWORKS				
A1	Radovi na objektu skladišta - PVC stolarija na skladištu Works on warehouse building - PVC joinery in the warehouse				

REKAPITULACIJA SVIH RADOVA RECAPITULATION OF ALL WORKS		
A1	Radovi na objektu skladišta - PVC stolarija na skladištu Works on warehouse building - PVC joinery in the warehouse	
	UKUPNO TOTAL	
	PDV 17% VAT 17%	
	SVEUKUPNO GROSS TOTAL	
	POPUST DISCOUNT	
	UKUPNA CIJENA SA POPUSTOM TOTAL PRICE WITH DISCOUNT	

Prije početka izvođenja radova, Izvođač radova je dužan uzeti mjere za sve bravarske pozicije. Izvođač radova je odgovoran za preuzete dimenzije.

Izvođač radova je dužan izvoditi radove u skladu sa važećim Zakonom o građenju i voditi gradilišnu dokumentaciju u skladu sa važećim Zakonom o građenju:

- Imenovati rukovodioca radova,
- Voditi građevinsku knjigu i građevinski dnevnik,
- Dostaviti dokaze o kvaliteteti ugrađenih materijala i bravarije,
- Dostaviti dokaze da je otpad zbrinuo na deponiji (račun ili potvrdu),
- Na kraju izvedenih radova dostaviti Izjavu da je radove izveo u skladu sa ponudom i dokaz o kvalitetu ugrađenih materijala.